RevNo	Revision note	Date	Signature	Checked

External fittings to be controlled by photo cell on landlords supply

Concrete Access Road

2No. 5ft HYDRA LED fittings by Dextra Lighting controlled by IP rated microwave motion sensor

Raised Concrete

Concrete Access Road

Bollard

Site Hoarding

External fittings to be controlled by photo cell on landlords supply

Allow additional Glotto fitting below, not shown.

Raised Concrete

Raised Concrete

EXI LED running man Emergency Escape luminaire by Dextra Lighting

Comms. Room

LEGEND

- A — RUNWAY LED 4K Linear luminaire by Dextra Lighting (Suspended @ 2.5m) Each length shall consist of 3x3m extrusions and 1x1.5m extruion. Allow 1 emergency module per length
- B — RUNWAY LED 4K Linear luminaire C/W R25c by Dextra Lighting (Flush Mounted)
- C — RUNWAY LED 4K Linear luminaire C/W R25c by Dextra Lighting (Surface Mounted)
- D — EPK LED by Dextra Lighting 5ft
- E — DENOTES EMERGENCY TYPE with 3 hours integral emergency pack
- F — Amed LED 4000k Surface mounted luminaire By Dextra Lighting (White)
- G — REALTA MICRO LED by Thorlux lighting
- H — REALTA LED by Thorlux lighting
- LED strip lighting by Dextra lighting
- J — LED 4 Emergency corridor luminaire by Dextra Lighting
- K — Mirror light by Sylvania 0053400
- 1 GANG LIGHT SWITCH
- 2 — 1 GANG 2 WAY LIGHT SWITCH
- D — RETRACTIVE SWITCH FOR DSI DIMMING
- EXIT — 3 HOUR NON MAINTAINED SIGN LIGHT

NOTES

These drawings shall be read in conjunction with the "Electrical Specification" by Rosiek Ltd

The contractor will be required to visit site prior to the submission of their tender documents. No additional costs will be accepted due to the contractors failure to carry out the specified pre-tender survey. All items shown or noted on these drawings together with the specification shall be included within the tendered sum

Conduit shall be of the galvanised steel type mounted flush behind new plasterboard ceilings and partitions. Surface mounted on existing brick work.

Before any materials are ordered or installation work commenced, the contractor shall put forward their containment proposals for discussion

Itemref	Quantity	Title/Name, designation, material, dimension etc			Article No./Reference	
Designed by Ben Jones		Checked by bj	Approved by - date N/A	Filename Preliminary	Date 04/09/17	Scale 1:50 @ A1
Rosiek Ltd				Basement Lighting Layout		
				Dwg. No. 17020-T-211	Edition	Sheet 1/1