

Legend

-	Project Boundary
	Enabling Works Active Site Boundary
	Overhead powerline
	Gas Main
	Surveyed Gas main
	Telecom
	Telewest
	Thus
	Cable & Wireless
	Combined Sewer
	Private Sewer
	Foul Sewer
	Combined NWL Sewer
	Foul Sewer
	Surface Sewer
	Watercourse
	Building drainage
	Preferred Sewer Diversion
	Surveyed Combined NWL Sewer
	Projected route-Combined NWL Sewer
	Surveyed Discharge Point
	Remaining Pitt Street Wall
	Remaining Areas of Concrete
٥.	Surveyed Mineshaft
•	Known Mineshaft
	Hotspot (below concrete)
0	Geo Thermal Borehole
Ð	Real Time Noise Monitoring Location
7	Capped Mineshaft

Groundwater Monitoring Location

Δ SP8

· 🗧 👝 Science Central Newcastle upon Tyne

• • • • • Science Central CENTRAL TO NEWCASTLE SCIENCE CITY

AS BUILT

Residual Hazards

DRAWING TI 1:1000 @ A1 DD 12.03.2014

> Hall Construction Services Limited

> > Stotforth Hill House Windlestone Rushyford County Durham **DL17 0NF** Tel: 01325 311013 Fax:01325 311571

Notes:

Services are indicative only and copied from 225057 -Brewery Demolition with the exception of known services surveyed on site as indicated on the drawing

Contractors must scan all areas in advance of any excavations commencing

All remaining areas of concrete are below agreed horizon

Refer to Mineshaft register for cap details

Remaining Hot spot situated under concrete floor

2031 PROJECT No.		DD265 DRAWING No.		B
REV	AMENDME	NT	DRAV	WN CHECKED
В	All remaining services, capped mineshafts, capped pipes, monitoring locations, remaining areas of concrete added; manhole cover levels amended 12.03.2014			DD
A	Shaft Cap No. 7; CAT Scanned Electric Cable (Corporation St) added; Remaining areas of concrete amended 27.09.2013			DD
				NOTES