	EXTERNAL WALLS				£	р
	The following works are to be read in conjunction with and comply fully with the NBS and all details and notes on Drawings E 17301 A 04 and E 17301 A 06, Preliminaries and General Conditions Refer to Preliminaries for the latest Drawing Revisions					
	External wall comprising 102.5mm facing brickwork outer leaf, 50mm air gap with 40mm partial fill insulation and 140mm blockwork inner leaf, including damp proof courses, closing cavities, and cutting, toothing bonding to existing structure					
Α	Generally	Item	1			
В	Extra for brick-on-edge soldier courses	Item	ı			
	Combined steel lintels (All Provisional)					
С	1.098m long (1 nr)	Item	ı			
D	1.053m long (1 nr)	Item	ı			
Е	1.548m long (1 nr)	Item	ı			
E1	2.11m long (5 nr)	Item	ı			
F	1.223m long (2 nr)	Item	ı			
	2.335m long (1 nr)	Item	ı			
G	4.135m long (1 nr)	Item	1			
	Non itemised works					
н	Allow here for all costs relating to works included on Drawings and in the NBS and Structural Specification but not itemised separately in this Section	Item	ı			
EXTERNAL WALLS TO PHASE 1 ELEMENTAL SUMMARY £						

17301 7 External Walls/1