

ELMS BANK SPECIALIST ARTS COLLEGE HYDROTHERAPY POOL		PHASE 1 NEW EXTENSION			
				£	p
<u>CONTACTOR DESIGN PORTION ANALYSIS (CDP Analysis)</u>					
<u>HYDROTHERAPY POOL INSTALLATIONS</u>					
<u>PRICED SUMMARY</u>					
ZD2000	Pool including the pool lining and supporting structure comprising base frame, panels and also including waterproof PVC strips / link plates				
ZD2010	Pool Staircase and Handrail				
ZD2020	Pool Bench				
ZD2030	Pool Ballet Bar				
ZD2040	Insulated Electrically Operated Pool Cover				
ZD3000	Balancing Tank				
ZD3010	Channels & Grating serving balancing tank including "L" Profile				
ZD3020	Pipework, Valves & Vacuum Point in connection with the Balancing Tank				
ZD23030	Pumps In connection with the Balancing Tank				
ZD3040	2nr Manholes in connection with the Balancing Tank				
ZD3050	All other Balancing Tank Works / Equipment				
ZD4000	Filtration Inlets To Pool				
ZD4010	All Pipework & Valves in connection with the Filtration Systems				
ZD4020	All Filtration System Pumps including Macerator Sump Pump				
ZD4030	Outlet Sumps				
ZD4040	Filtration system UV Unit				
ZD4050	Flocculation Station				
ZD4060	All Backwash Drainage				
ZD4070	Pellet Pro Unit & Dosing Pumps				

ZD4080	CO2 Dosing System & Cylinders				
ZD4090	Pool Hydro jets				
ZD4100	All Chemicals Required including 1 months Supply after practical completion				
ZD4110	Bib Taps & Hoses to 2nr Chemical Stores				
ZD4120	All Other Pool Filtration Works / Equipment				
ZD4130	Compliance with PWTAG etc				
ZD5000	Underwater Pool Lighting				
ZD5010	Electrical Equipment Relating To Filtration Systems				
ZD5020	Electrical Supplies and Conduit To All Other Plant and Equipment				
ZD5030	All Bonding Works Required In Connection With All Equipment including Pool Structure, Staircase, Handrails etc				
ZD6000	Pool Heating System complete as Employer's Requirements Including Drawing SLP2012-01.01				
ZD7000	Changes To Designs And Works Included On Mechanical Engineers Services Drawings & Specifications To Meet The Employer's Requirements For Ventilation in connection with the Hydrotherapy Pool Installation (see Employer's Requirements drawings SLP2012-21.01)				
ZD7500	Insulation To Pool Structure, Pipework, Pipework Accessories, Equipment Etc				
ZD8000	Ladder To Pump Pit				
ZD8010	Safety Handrailing To Pump Pit				
ZD8020	Davit Hoist To Pump Pit				
ZD8030	Allow For Extra Over Costs For Changes To Designs And Works Included On Structural Engineers Drawings To Meet The Employer's Requirements For The Hydrotherapy Pool Installation. The Changes In Designs And Works Include Adjustment To Pump Pit Depth, Hardcore, Backfill Materials, Pea Gravel, Concrete Bases, Plinths, Structures Serving The Pool, Pool Sumps and Balance Tank (see Employer's Requirements drawings SLP2012-00.01 & SLP2012.20.02)				
ZD8040	PVC Membrane Below Surrounding Floor Finishings				
ZD8050	Grouting To Pool Structure				
ZD8060	Soundproofing of Pool Plant Room				
ZD8070	Back Wash Drainage Connections				
ZD8080	Plinths Serving Pumps, Strainers, Heat Exchangers etc				

ZD8090	Trenches where required				
ZD8100	All Internal And External Safety / Emergency Action Notices together with No Smoking and Hazard Warning Signage Relating To Pool and Pool Plant Rooms				
ZD8110	Effluent Drainage				
ZD8120	Allow For Additional Builders Work Requirements As Specified On The Employer's Requirements Drawings / Specifications But Not Listed Above				
ZD8130	Allow For Other Builders Work Requirements Not Specified On The Employer's Requirements Drawings / Specifications But Required By The Specialist Pool Installer To Complete The Hydrotherapy Pool Installations				
ZD8500	Allow For Testing and Commissioning All Systems, Installations and Equipment Relating To The Hydrotherapy Pool and Pool Plant & Chemical Store Rooms				
ZD8510	Pipe Test certificates				
ZD8520	Allow for providing Operating Manual, Commissioning Handover Certificates & "As Fitted" Drawings etc				
ZD9000	Allow for other works relating to The Hydrotherapy Pool Installation which are included within Employer's Requirements, drawings and specifications but not listed above				
ZD9500	Allow here for working outside the Contractor's Site Boundary in order to complete the Hydrotherapy Pool Installation				
TOTAL TO CDP ANALYSIS SUMMARY £					-