

				£	p
<b>INTERNAL WALLS AND PARTITIONS</b>					
<p>The following works are to be read in conjunction with and comply fully with the NBS and all details and notes on Drawing E 17301 A 04, Preliminaries and General Conditions</p> <p>Refer to Preliminaries for the latest Drawing Revisions</p> <p>100mm blockwork partitions / walls, built up to 200mm above level of suspended ceiling, including damp proof courses, and cutting, toothing and bonding to existing structure</p>					
A	Generally	Item			
140mm blockwork walls, built up to underside of roof structure, including damp proof courses, and cutting, toothing and bonding to existing structure					
B	Generally	Item			
Precast concrete lintels (All Provisional)					
C	100mm x 150mm x 1.2m (2 nr)	Item			
D	140mm x 150mm x 1.31m (6 nr)	Item			
E	140mm x 225mm x 1.31m (11 nr)	Item			
F	140mm x 225mm x 2.15m (1 nr)	Item			
G	140mm x 225mm x 2.4m (2 nr)	Item			
Non itemised works					
H	Allow here for all costs relating to works included on Drawings and in the NBS but not itemised separately in this Section	Item			
		Item			
		Item			
<b>INTERNAL WALLS AND PARTITIONS TO PHASE 1 ELEMENTAL SUMMARY £</b>					
					-