	WALL FINISHES  The following works are to be read in conjunction with and comply fully with the NBS and all details and notes on Drawing E 17301 A 17, Preliminaries and General Conditions Refer to Preliminaries for the latest Drawing Revisions		£ p
	13 mm thick plaster to new blockwork, including work to narrow widths, beads and all labours		
	To new walls and partitions		
Α	Staff Change 1 - R01	Item	
В	Staff Change 2 - R02	Item	
С	Corridor and Lobby to Pool - R03	Item	
D	Wet Change 1 and Lobby - R04		
Е	Accessible Toilet - R05	Item	
F	Wet Change 2 and Lobby - R06		
G	Accessible Toilet - R07	Item	
Н	Corridor - R08	Item	
1	Hydrotherapy Pool Hall - R09	Item	
J	Equipment Store - R10		
К	Change 1 - R11	Item	
L	Dry Change 2 and Lobby - R12	Item	
М	Accessible Toilet - R13	Item	
N	Showers - R14		
0	Dry Change 3 and Lobby - R15	Item	
Р	Accessible Toilet - R16	Item	
Q	Showers - R17		
R	Laundry - R18	Item	
S	Entrance Lobby - R19	Item	
Т	Office - R20	Item	
U	Pool Plant Room - R21	Item	
V	Chemical Store 1 - R22	Item	
W	Chemical Store 2 - R23	Item	
 170	l 01 11 Wall Finishos/1	1 1	II I

17301 11 Wall Finishes/1

				£	р
Х	Plant Room - R24	Item			
	13 mm thick plaster to existing brickwork, including raking out joints and hacking to form key, dubbing out as necessary, work to narrow widths, beads, all labours and fair joints to existing				
	To existing walls				
Υ	Staff Change 1 - R01	Item			
Z	Staff Change 2 - R02	Item			
AA	Corridor and Lobby to Pool - R03	Item			
AA1	Wet Change 2 Lobby - R06	Item			
AB	Accessible Toilet - R07	Item			
AC	Corridor - R08	Item			
AD	Dry Change 3 and Lobby - R15	Item			
AE	Accessible Toilet - R16	Item			
	Reference W 3 - Altro Whiterock Chameleon coloured UPVC cladding, including work to narrow widths and trims				
AF	Wet Change 1 and Lobby - R04	Item			
AG	Wet Change 2 and Lobby - R06	Item			
АН	Hydrotherapy Pool - R09 and Equipment Store - R10	Item			
Al	Showers - R14	Item			
AJ	Showers - R17	Item			
AJ1	To walls between 2.1m height noted on Drawings and full ceiling height (25 m2 - Provisional)	Item			
AJ2	To projecting steel columns, pipe casings and the like	Item			
	100mm x 20mm (approx finished size) timber skirting to match existing, including short lengths and all labours				
AK	Corridor and Lobby to Pool - R03	Item			
AL	Corridor - R08	Item			
AM	Laundry - R18	Item			
AN	Entrance Lobby - R19	Item			
AO	Office - R20	Item			
AP	Pool Plant Room - R21	Item			
AQ	Chemical Store 1 - R22	<del>ltem</del>			

17301 11 Wall Finishes/2

			£ p	1
AR	Chemical Store 2 - R23	<del>Item</del>		
AS	Plant Room - R24	Item		
	All Provisional - Provide and fix 150 x 150 x 6mm thick white ceramic glazed wall tiles including grouted joints			
AS1	900mm wide x 3 courses high above wash hand basins and Belfast sink – 8nr total	Item		
AS2	600mm wide x 6 courses high behind appliances – 2nr total	Item		
AS3	3 courses high above worktops and sink tops – 10m total	Item		
AS4	to full height of the room around shower areas, 5m2 per shower location - 3nr locations	Item		
	Handrails / Guardrails (All Provisional)			
	Gradus Wall Protection Stystem, Dual rail 3400T Oak handrail / Sienna 009 Guardrail			
AS5	Generally, in varying lengths (80 m)	Item		
AS6	Mounting bracket (300 nr)	Item		
AS7	Universal return (100 nr)	Item		
AS8	External corner (20 nr)	Item		
AS9	Internal corner (20 nr)	Item		
AS10	Universal end cap (40 nr)	Item		
	Non itemised works			
АТ	Allow here for all costs relating to works included on Drawings and in the NBS but not itemised separately in this Section	Item		
	TO PHASE 1 ELE	WALL FINISHES MENTAL SUMMARY		$\frac{1}{2}$

11 Wall Finishes/3