

				£	p
	WALL FINISHES				
	The following works are to be read in conjunction with and comply fully with the NBS and all details and notes on Drawing E 17301 A 17, Preliminaries and General Conditions				
	Refer to Preliminaries for the latest Drawing Revisions				
	13 mm thick plaster to new blockwork, including work to narrow widths, beads and all labours				
	To new walls and partitions				
A	Staff Change 1 - R01	Item			
B	Staff Change 2 - R02	Item			
C	Corridor and Lobby to Pool - R03	Item			
D	Wet Change 1 and Lobby - R04				
E	Accessible Toilet - R05	Item			
F	Wet Change 2 and Lobby - R06				
G	Accessible Toilet - R07	Item			
H	Corridor - R08	Item			
I	Hydrotherapy Pool Hall - R09	Item			
J	Equipment Store - R10				
K	Change 1 - R11	Item			
L	Dry Change 3 and Lobby - R12	Item			
M	Accessible Toilet - R13	Item			
N	Showers - R14				
O	Dry Change 2 and Lobby - R15	Item			
P	Accessible Toilet - R16	Item			
Q	Showers - R17				
R	Laundry - R18	Item			
S	Entrance Lobby - R19	Item			
T	Office - R20	Item			
U	Pool Plant Room - R21	Item			
V	Chemical Store 1 - R22	Item			
W	Chemical Store 2 - R23	Item			

				£	p
X	Plant Room - R24	Item			
	13 mm thick plaster to existing brickwork, including raking out joints and hacking to form key, dubbing out as necessary, work to narrow widths, beads, all labours and fair joints to existing				
	To existing walls				
Y	Staff Change 1 - R01	Item			
Z	Staff Change 2 - R02	Item			
AA	Corridor and Lobby to Pool - R03	Item			
AB	Accessible Toilet - R07	Item			
AC	Corridor - R08	Item			
AD	Dry Change 3 and Lobby - R15	Item			
AE	Accessible Toilet - R16	Item			
	Reference W 3 - Altro Whiterock Chameleon coloured UPVC cladding, including work to narrow widths and trims				
AF	Wet Change 1 and Lobby - R04	Item			
AG	Wet Change 2 and Lobby - R06	Item			
AH	Equipment Store - R10	Item			
AI	Showers - R14	Item			
AJ	Showers - R17	Item			
	100mm x 20mm (approx finished size) timber skirting to match existing, including short lengths and all labours				
AK	Corridor and Lobby to Pool - R03	Item			
AL	Corridor - R08	Item			
AM	Laundry - R18	Item			
AN	Entrance Lobby - R19	Item			
AO	Office - R20	Item			
AP	Pool Plant Room - R21	Item			
AQ	Chemical Store 1 - R22	Item			
AR	Chemical Store 2 - R23	Item			
AS	Plant Room - R24	Item			
	Non itemised works				

AT	Allow here for all costs relating to works included on Drawings and in the NBS but not itemised separately in this Section				Item			£	p
WALL FINISHES									
TO PHASE 1 ELEMENTAL SUMMARY £									-