

				£	p
	CEILINGS				
	The following works are to be read in conjunction with and comply fully with the NBS and all details and notes on Drawing E 17301 A 17, Preliminaries and General Conditions				
	Refer to Preliminaries for the latest Drawing Revisions				
	Reference C1 - Armstrong Dune Evo Max 600mm x 600mm Tegular ceiling tiles with Prelude 24 TLS suspension system				
A	Corridor and Lobby to Pool - R03	Item			
B	Corridor - R08	Item			
C	Entrance Lobby - R19	Item			
D	Office - R20	Item			
	Reference C2 - Armstrong Ceramaguard 600mm x 600mm Tegular ceiling tiles with Prelude 24CR TLX corrosion-resistant suspension system				
E	Hydrotherapy Pool Hall - R09	Item			
F	Equipment Store - R10	Item			
	Reference C3 - Armstrong Hydroboard 600mm x 600mm Tegular ceiling tiles with Prelude 24CR corrosion-resistant suspension system				
G	Staff Change 1 - R01	Item			
H	Staff Change 2 - R02	Item			
I	Wet Change 1 and Lobby - R04	Item			
J	Accessible Toilet - R05	Item			
K	Wet Change 2 and Lobby - R06	Item			
L	Accessible Toilet - R07	Item			
M	Change 1 - R11	Item			
N	Dry Change 3 and Lobby - R12	Item			
O	Accessible Toilet - R13	Item			
P	Showers - R14	Item			
Q	Dry Change 2 and Lobby - R15	Item			
R	Accessible Toilet - R16	Item			
S	Showers - R17	Item			

				£	p
T	Laundry - R18		Item		
	Reference C4 -Plasterboard and skim to timber joists, including work to narrow widths and all labours				
U	Chemical Store 1 - R22		Item		
V	Chemical Store 2 - R23		Item		
	Access panels in ceiling Reference C1				
W	1200mm x 600mm (1 nr)		Item		
X	1200mm x 1200mm (1 nr)		Item		
	Access panels in ceiling Reference C3				
Y	1200mm x 1200mm (2 nr)		Item		
	Non itemised works				
Z	Allow here for all cost relating to works included on drawings and in the NBS but not itemised separately in this Section		Item		
CEILINGS					
TO PHASE 1 ELEMENTAL SUMMARY £					-