

				£	p
<b>DRAINAGE</b>					
<p>The following works are to be read in conjunction with and comply fully with the NBS and all details and notes on Drawing 29387-620, -665, -666 and -680, Preliminaries and General Conditions</p> <p>Refer to Preliminaries for the latest Drawing Revisions</p>					
<b>SURFACE WATER DRAINAGE</b>					
Drains, including excavation, granular beds and surrounds, concrete beds and surrounds (all drainage pipework under the new extension to have concrete beds and surrounds), pipes and fittings and backfilling, and all connections to					
A	Drain between Corridor and existing drain adjacent Pool, including gulley	Item			
B	Drain between Wet Change 1 Lobby and existing drain, including gulley	Item			
C	Drain and branch between Link Corridor Circulation and MAC SW 1, including rodding eye and gulley				
D	Drain and branch between Pool Equipment Store and MAC SW 1, including gulley	Item			
E	Drain between MAC SW 1 and MAC SW 2	Item			
F	Drain between Plant Room Pit and existing drain adjacent PPIC FW 2, including gulley	Item			
G	Drain between Chemical Store and MAC SW 3, and branch drain from Entrance Lobby, including gulleys	Item			
H	Drain between MAC SW 3 and MAC SW 4	Item			
I	Drain between Plant Room and MAC SW 4, including gulley	Item			
	Chambers, as detailed, including excavation, concrete beds and surrounds and backfilling				
J	MAC SW 1	Item			
K	MAC SW 2, built on existing drain, including temporary diversions as necessary	Item			
L	MAC SW 3	Item			
M	MAC SW 4, built on existing drain, including temporary diversions as necessary	Item			
<b>FOUL WATER DRAINAGE</b>					
Drains, including excavation, granular beds and surrounds, concrete beds and surrounds (all drainage pipework under the new extension to have concrete beds and surrounds), pipes and fittings and backfilling, and all connections to					

N	Drains (2 nr) between Accessible Toilet and MAC FW 1, including adaptors and bends	Item
O	Drain between MAC FW 1 and MAC FW 2	Item
P	Drain and branch between Accessible Toilet and MAC FW 2, including adaptors and bends	Item
Q	Drain between MAC FW 2 and MAC FW 3	Item
R	Drain and branches between Showers and MAC FW 3, including adaptors and bends	Item
S	Drain between MAC FW 3 and MAC FW 4	Item
T	Drain between MAC FW 4 and MAC FW 5	Item
U	Drain between Showers and MAC FW 5	Item
V	Drain between MAC FW 5 and MAC FW 6	Item
W	Drain between Showers and MAC FW 6	Item
X	Drain between MAC FW 6 and MAC FW 7	Item
Y	Drain between Showers and MAC FW 7	Item
Z	Drain between MAC FW 7 and MAC FW 8	Item
AA	Drain and branches between Change 1 and Laundry and MAC FW 8, including adaptors and bends	Item
AB	Drain between MAC FW 8 and MAC FW 9	Item
AC	Drain between MAC FW 9 and PPIC FW 1	Item
AD	Drains between Pool Plant Room and PPIC FW 1	Item
AE	Drain between PPIC FW 1 and PPIC FW 2	Item
AF	Drains between Pool Plant Room and drain between PPIC FW 1 and PPIC FW 2	Item
AG	Drain between Pool Plant Room Pit and drain between PPIC FW 1 and PPIC FW 2, including non-return valve	Item
AH	Drains between Pool Plant Room and PPIC FW 2	Item
AI	Drain between PPIC FW 2 and FW MH 1	Item
AJ	Drain between FW MH 1 and Pump Station	Item
AK	Drain between Pump Station and PPIC FW 3 (rising main)	Item
AL	Drain between PPIC FW 3 and EX MH 8	Item
AM	Drains (2 nr) between Poolside Showers and MAC FW 11	Item

AN	Drain between Wet Change 1 and MAC FW 12	Item		
AO	Drain between Wet Change 2 and MAC FW 12	Item		
AP	Drains (2 nr) between Wet Change 1 Accessible Shower and existing drain	Item		
AQ	Drain and branch between Wet Change 2 Accessible Shower and MAC FW 16, including adaptors and bends	Item		
	Chambers, as detailed, including excavation, concrete beds and surrounds and backfilling			
AR	MAC FW 1	Item		
AS	MAC FW 2	Item		
AN	MAC FW 3	Item		
AO	MAC FW 4	Item		
AP	MAC FW 5	Item		
AQ	MAC FW 6	Item		
AR	MAC FW 7	Item		
AS	MAC FW 8	Item		
AT	MAC FW 9	Item		
AU	PPIC FW 1	Item		
AV	PPIC FW 2	Item		
AW	FW MH 1	Item		
AX	Pump Station	Item		
AY	PPIC FW 3	Item		
AZ	MAC FW 11, built on existing drain, including temporary diversions as necessary	Item		
BA	MAC FW 11, built on existing drain, including temporary diversions as necessary	Item		
BB	MAC FW 11, built on existing drain, including temporary diversions as necessary	Item		
	<b>FOUL WATER DRAINAGE BEYOND THE SITE BOUNDARY</b>			
	<b>Works to be carried out strictly outside School hours</b>			
	Drains, including excavation, granular beds and surrounds, concrete beds and surrounds, pipes and fittings and backfilling, and all connections to soil pipes, chambers and existing drains (Note: Drain runs partly within the Site Boundary)			

BC	Drains between Staff Changes and MAC FW 13, including adaptors and bends	Item	
BD	Drains between Staff Changes and MAC FW 14, including adaptors and bends	Item	
BE	Drain between Staff Change and MAC FW 15	Item	
	Chambers, as detailed, including excavation, concrete beds and surrounds and backfilling		
BF	MAC FW 13, built on existing drain, including temporary diversions as necessary	Item	
BG	MAC FW 14, built on existing drain, including temporary diversions as necessary	Item	
BH	MAC FW 15, built on existing drain, including temporary diversions as necessary	Item	
	Temporary Works and Making Good		
BI	Allow for the following		
	Protecting the existing structure	Item	
BJ	Dust-proof screens	Item	
BK	Reinstating and making good any part of the structure disturbed	Item	
BL	Reinstating and making good floor finishings, wall finishings and decoration to match existing	Item	
	<b>FOUL WATER PUMP STATION</b>		
	Pump station, as detailed, including excavation and backfilling, and all connections		
BM	As ITT Flygt Drawing F2.75218 A and Pump Supplies Limited quotation dated 16 February 2018 (included as Documents S1 and S2)	Item	
	Non itemised works		
BN	Allow here for all costs relating to works included on Drawings and in the NBS but not itemised separately in this Section	Item	
		<b>DRAINAGE</b>	
<b>TO PHASE 1 ELEMENTAL SUMMARY £</b>			-