

EXTERNAL WORKS			£	p
<p>The following works are to be read in conjunction with and comply fully with the NBS and all details and notes on Drawing E 17301 A 18, Drawing 29387-680, Preliminaries and General Conditions</p> <p>Refer to Preliminaries for the latest Drawing Revisions</p>				
Site Clearance				
Carefully remove and store securely on site for subsequent re-use				
A	Fencing and gates	Item		
Kerbs				
B	Kerbs to match existing, straight and to radius, including excavation and disposal of site, preparation, concrete bases and haunching courses and fair joints to existing	Item		
Pavings				
C	Road Specification tarmac to falls and cross-falls, including excavation and disposal of site, preparation, sub-base, base and wearing courses and fair joints to existing	Item		
D	Pedestrian crossing in thermoplastic marking	Item		
E	Pedestrian Specification tarmac to falls and cross-falls, including excavation and disposal of site, preparation, sub-base, base and wearing courses and fair joints to existing	Item		
F	Dropped kerbs with pimple paving	Item		
Fencing and gates				
G	Take from store and reinstall fencing and gates, including excavation and disposal off site, concrete, modification as required and new fixings and fittings as necessary			
G1	Allow extra over refixing existing fencing costs for providing and fixing new fencing complete to match the existing fencing in every respect	Item		
Non itemised works				
H	Allow here for all costs relating to works included on Drawings and in the NBS but not itemised separately in this Section	Item		
EXTERNAL WORKS				
TO PHASE 1 ELEMENTAL SUMMARY £				-