| | EXTERNAL WORKS | | | £ | р |
|--------------------------------|---|-----|-----|---|---|
| | The following works are to be read in conjunction with and comply fully with the NBS and all details and notes on Drawing E 17301 A 18, Drawing 29387-680, Preliminaries and General Conditions Refer to Preliminaries for the latest Drawing Revisions | | | | |
| | Site Clearance | | | | |
| | Carefully remove and store securely on site for subsequent re-use | | | | |
| Α | Fencing and gates | It | tem | | |
| | Kerbs | | | | |
| В | Kerbs to match existing, straight and to radius, including excavation and disposal of site, preparation, concrete bases and haunching courses and fair joints to existing | It | tem | | |
| | Pavings | | | | |
| С | Road Specification tarmac to falls and cross-falls, including excavation and disposal of site, preparation, sub-base, base and wearing courses and fair joints to existing | lt | tem | | |
| D | Pedestrian crossing in thermoplastic marking | It | tem | | |
| Е | Pedestrian Specification tarmac to falls and cross-falls, including excavation and disposal of site, preparation, subbase, base and wearing courses and fair joints to existing | II | tem | | |
| F | Dropped kerbs with pimple pavings | It | tem | | |
| | Fencing and gates | | | | |
| G | Take from store and reinstall fencing and gates, including excavation and disposal off site, concrete, modification as required and new fixings and fittings as necessary | | | | |
| | Non itemised works | | | | |
| Н | Allow here for all costs relating to works included on Drawings and in the NBS but not itemised separately in this Section | l 1 | tem | | |
| . ! | EXTERNAL WORKS TO PHASE 1 ELEMENTAL SUMMARY £ | | | | |
| IO PRASE I ELEMENTAL SUMMARY E | | | | | - |