

Scope of Works Summary Document

Number	Quantity	Item	Notes	Drawing reference
1	As required	Substations	1,000 kVA Brick Built Substations (Locations shown on site layout plan)	4101-AXM-ZZ-00-DR-A-4050!C2!Sub-station
2	As required	LV cable networks		OHH-LOWER ACRE_381 EVC CONNECTIONS_240205
3	269	House service connections	See accommodation schedule. Heating – 6kW Ground Source Heat Pump.	OHH-LOWER ACRE_381 EVC CONNECTIONS_240205
4	112	Apartment service connections	See accommodation schedule. Heating – 6kW Ground Source Heat Pump	OHH-LOWER ACRE_381 EVC CONNECTIONS_240205
5	9	Apartment BNO supplies	Loadings as per accommodation schedule	OHH-LOWER ACRE_381 EVC CONNECTIONS_240205
6	381	7kW SMART EV Charger	Wired to individual dwelling electric meters	OHH-LOWER ACRE_381 EVC CONNECTIONS_240205
7	2	3-Phase 50kVA	Sewage Pumping Station Supplies	
8	101	Unmetered streetlight connections	Highways Authority Adopted – Link Road unmetered streetlight connections	SSE296001-LD-001!H!Lighting_Layout
9	16	Unmetered streetlight connections	Highways Authority Adopted – Internal Distributor Road unmetered streetlight connections	EVO20010364-LD-001-A Spine Road
10	79	Metered streetlight connections	Lower Acre Private Roads – Metered streetlight connections	EVO20010723-LD-001-A Parcel 1.1
				EVO20010723-LD-101-B Parcel 1.1
				EVO20011211-LD-001-A Parcel 1.2
				EVO20011211-LD-101-B Parcel 1.2
11	3	Unmetered illuminated street sign connections	Highways Authority Adopted – Link Road unmetered street sign connections	10413-SEG_3-236!C1! SIGNING CONNECTIONS 01 & 02
				10413-SEG_3-232!C1! SIGNING CONNECTIONS 03
12	8	1-Phase metered feeder pillar connections	Bus shelters	10413-SEG_3-202!_C1! - Bus Shelter R3-01
				10413-SEG_3-203!_C1! - Bus Shelter R3-02
				10413-SEG_3-206!_C1! - Bus Shelter R3-03 & R3-04
				10413-SEG_3-209!_C1! - Bus Shelter R3-05 & R3-06
				5015560-RDG-XX-ST-DR-C-0020 - Bus Shelters LA-01 & LA-02
13	4	Temporary Builder's Supply (TBS)	3 Phase 69KVA	