



Date 16.02.18

Quotation by Javier.gonzalez@sutcliffe.co.uk

For the attention of J. Gonzalez.

Dear Javier

Ref: – Foul Water Pumping Tank – Elms Bank.

With reference to the above scheme we thank you for your recent enquiry and are pleased to submit our quotation for your approval; we have based our quotation on the information supplied.

**QUOTATION - Supply, and commission the following:**

1 Off ITT Flygt Topps100s submersible packaged pumping tank, measuring 1500w x 4000d.  
Incorporating the following equipment;-  
2 x DP 3085 Submersible pumps, 2.0, 415v, 3ph, 50hz.  
2 x Discharge stools 65mm.  
4 x Guide rails and brackets.  
1 x Off set off steel discharge pipe work and valves 65mm PN16.  
1 x Duel control panel and weatherproof GRP kiosk, c/w beacon.  
1 x Off Set of Level control floats.  
1 x Compression coupling for 90mm HPPE Sdr17 rising main.  
1 x Access cover and frame.5 tonne rated. [Supply only].

**Quotation**

To supply, and commission pumping equipment as described above.  
£10,230.00 plus vat

**Additional Quotation.**

Delivery to site FOC, off-loading by others.  
Commission and testing of the pumping system £430.00

Delivery 2 to 3 weeks from official order.

**Notes / Comments**

A suitably sized 415v, 3ph electrical supply will be made available for connection.  
All civil work and ducting requirements by others.  
A 90mm HPPE sdr 17 rising main has been used for our calculations.  
Rising main supplied and connected by others.  
Installation by others is carried out in strict accordance with supplied instructions.  
We have included for all site visits prior to commencement.  
The control kiosk is positioned within 10mtrs of the well.  
Supply and testing of main by others.  
Our offer is valid for 6months from date of tender.  
Pump Supplies Ltd general terms and conditions apply to this tender.

We trust the above is of interest and look forward to receiving further instructions.

Yours Sincerely  
On Behalf of Pump Supplies Ltd

*Dave Fletcher*