

Date: 13 October 2022
 Contract: 22905 - Biggins Wood, Folkestone
 Document: Quotation for the construction of a reptile exclusion barrier - revision 1

John F Hunt Regeneration Ltd
 London Road
 Grays, Essex
 RM20 4DB

<u>ITEM</u>	<u>DESCRIPTION</u>	<u>QTY</u>	<u>UNIT</u>	<u>RATE</u>	<u>TOTAL</u>	<u>REMARKS</u>
	<u>Construction of a 756m polythene reptile exclusion barrier to site boundary</u>					Expected production: 100 lin.m./day
PLT	3t excavator	8.00	day			CECA '22 rate
PLT	30kW trencher	8.00	day			CECA '22 rate
LAB	Excavator operator	8.00	day			
LAB	2 no. skilled labourer	8.00	day			
LAB	E/O skilled labourer for western section	2.00	day			Additional labourer added - This cost is a function of us having to do the work twice over should we receive instruction (once to do the fence, and again when we come to do the full site clearance between the existing and boundary fence later on).
LAB	Manager to supervise					
MAT	2% UV stabilised, 1000 gauge polythene sheet	756.00	m			
MAT	Protective Washers (25mm diameter)	3000.00	no			
MAT	Extra Wide Head Clout Nails (galvanised 30mm long)	3000.00	no			
MAT	Timber Support Posts - 1.2M x 47mm x 47mm - Treated and pointed one end	304.40	no			2.5 m centres
SUBCON	Ecologist in attendance	1.00	sum			see quote
	Risk contingency – in case ecologist prevents the regular progress of the works; 3 days of plant & labour cost allowance made					
	12% Contractor's Fees - does not apply to plant costs & risk allowance					
TOTAL EXC. VAT					£24,431.73	

Qualifications

The scope of works is based on information provided to date by the employer
 We have not applied any preliminary costs, or additional time, on the basis that this work will run concurrently with contract works (therefore not affecting the critical path), should this work affect the completion date, or require additional preliminary resources, we will issue the relevant notices/claims
 Lead in time for materials - 1 week
 Should the regular progress of the quoted works be prevented due to ecological reasons, then the direct costs that have been incurred or expected to incur (due to the disruption) will be claimable as loss and expense under cl. 4.19.1. of the contract agreement