

ANNEX 2

SCHEDULE OF WORKS

UGGLE LANE FOOTPATH IMPROVEMENTS

Item	Description	Quantity	Unit	Rate	Value
1	Clean off and prepare existing stone footpath approx. 170m long x 1.5m wide	170	Lin m		
2	Provide new "top surface" to existing stone footpath 170m long x 1.5 m wide, to include approx. 100 base and 25mm surface layer of compacted stone	170	Lin m		
3	Provide new section of footpath 15m long x 1.5m wide as access to seating area. To include geotextile membrane, sub-base, finished surface (6mm to Dust) and timber edging where required.	15	Lin m		
4	Provide 1No. new passing areas of new footpath construction to be 2.5m x 3.0m – location to be confirmed	7.5	Sq m		
5	Provide new footpath/hardstanding area (including geotextile membrane sub-base and surface finish (6mm to dust) at access point from A6 to facilitate gate and turning area for mobility scooters. Total area approx. 6m x 6m	36	Sq m		
6	Provide new section of footpath 10m long x 1.5m wide as access to seating area. To include geotextile membrane, sub-base, finished surface (6mm to Dust) and timber edging where required.	10	Lin m		
7	Provide additional turning area (Uggle Lane end of footpath) approx. 2.5m x 3.0m location to be confirmed	7.5	Sq m		
8	Provide new gate and fencing	1	No.		
9	Provide 3No. new soakaways Approx 1m x 2m x 600mm deep	3	No.		

Please note that all dimensions are approximate and will need to be confirmed on site before works commence.