



## **Swindon Borough Council**

### **Zurich Drainage Connections**

#### **Issue and Revision Record**

**Document Reference:** FWB Blvd-ATK-GEN-ZS-BQ-QS-000001

<b>Rev.</b>	<b>Date</b>	<b>Originator</b>	<b>Checked</b>	<b>Approved</b>	<b>Description</b>
P01	01/05/2020	PG	MM	MM	First Issue

[illegible]

Swindon Borough Council  
 Zurich Drainage Connections  
 BILL OF QUANTITIES

Item	Description	Quantity	Unit	Rate	Total
A	<b><u>Series 200: Site Clearance</u></b>				
	<b><u>Site Clearance</u></b>				
	General site clearance	1	Item		
Total Carried Forward to Main Summary					£ -

Swindon Borough Council  
Zurich Drainage Connections  
BILL OF QUANTITIES

Item	Description	Quantity	Unit	Rate	Total
<b><u>Series 500: Drainage and Service Ducts</u></b>					
<b>Drains and Service Ducts (Excluding Filter Drains, Narrow Filter Drains and Fin Drains)</b>					
A	150mm internal diameter drain; vitrified clay; on bed type S; in trench; depth to invert not exceeding 2 metres; average depth to invert 1.825 metres (SWS MH18 to TWMH 1904)	8	m		
B	150mm internal diameter drain; vitrified clay; on bed type S; in trench; depth to invert exceeding 2 metres but not exceeding 4 metres; average depth to invert 2.100 metres (SWS MH15 to TWMH 1906)	7	m		
C	150mm internal diameter drain; vitrified clay; on bed type S; in trench; depth to invert exceeding 2 metres but not exceeding 4 metres; average depth to invert 2.275 metres (FWS MH14 to TWMH Manhole)	10	m		
<b>Connections</b>					
D	Connection of 150mm internal diameter to existing chamber; depth to invert not exceeding 2 metres (Detail A)	1	Nr		
E	Connection of 150mm internal diameter to existing chamber; depth to invert exceeding 2 metres but not exceeding 4 metres (Detail B)	1	Nr		
F	Connection of 150mm internal diameter to existing chamber; depth to invert exceeding 2 metres but not exceeding 4 metres (Detail C)	1	Nr		
<b>Excavation in Hard Material</b>					
G	Extra over excavation for excavation in Hard Material in drainage	9	m3		
Total Carried Forward to Main Summary					

May 2020

**Total - Main Summary - Carried Forward to Form of Tender**