



Working together

**Installation of FRP bridge**  
**REFERENCE: DN334951**  
**PROCUREMENT PROCEDURE: UK OPEN**

**Supplier Response Document**  
**Part H - Price**

<b>Name of Tenderer:</b>	<<Complete full name of tenderer submitting the information>>	
<b>Deadline for submission:</b> (UK date and time)	<b>DATE:</b>	30 September 2018
	<b>TIME:</b>	23:30

<b>Status:</b>	ISSUED
<b>Version:</b>	1.00
<b>Date:</b>	31/08/2018

**Instructions for Tenderers:**

Tenderers are referred to the Invitation to Tender for full instructions and information on how price will be evaluated.

Please ensure that all pricing is submitted in GBP exclusive of VAT.

Cells filled BLUE must be completed by the Tenderer.

Completed tender documents must be submitted in accordance with the instructions given in the Invitation to Tender.

All items to be priced with reference to the specification, tender documents and all drawings:

Item	Description	Quantity	Unit	Rate	£ Total
<b>1.0</b>	<b>Preliminaries</b>				
1.1	Overheads and prelims costs, to include for all welfare, works compounds, safety fencing and tree protection.	1	item		£ -
1.2	Include for all Network rail site visits and inspections that may be required in their consent for the works.	2	item		£ -
1.3	Allow for management of the water level in the lagoon for the most effective construction and works operation.	1	item		£ -
<b>Sub-total</b>					<b>£ -</b>
<b>2.0</b>	<b>Demolition/Clearance</b>				
2.1	Remove temporary scaffolding footbridge and all supports, ramps and tarmac surfacing	1	item		£ -
2.2	Remove chain link fence to lagoon edge and railings to north side of original bridge and 2No. Gates to sluice gate compound	1	item		£ -
2.3	Concrete bridge and 2No. In situ mass concrete beams	1	item		£ -
2.4	Tree works to allow access, eg lower limb removal on Poole Park side of railway fence	1	item		£ -
<b>Sub-total</b>					<b>£ -</b>
<b>3.0</b>	<b>Construction</b>				
3.1	2No. New RC Abutment Cill beams	1	item		£ -
3.2	Installation via mechanical handling of delivered FRP bridge and all related preparatory work	1	item		£ -
3.3	Parapet railings installed to both sides of the new bridge	14.3	m		£ -
3.4	Replacement chain link fencing and gate to southern side to meet Network Rail specifications	1.6	m		£ -
3.5	New gate to sluice compound to match parapet	1	item		
3.6	New railings to lagoon edge	20.4	m		£ -
3.7	New gravel surface to marry levels between new bridge and existing path	89.5	m <sup>2</sup>		£ -
3.8	Consolidate and fill voids behind lagoon walls behind pilasters	1	item		£ -
<b>Sub-total</b>					<b>£ -</b>
<b>4.0</b>	<b>Restoration</b>				
4.1	Restore 2No. Brick pilasters following the stated conservator guidance, including the careful removal and restoration of capstones and brickwork for re-use.	1	item		£ -
4.2	Make repairs to damaged or missing brickwork and repoint as required	1	item		£ -
4.3	Rebuild brickwork and replace with restored capstones	1	item		£ -
<b>Sub-total</b>					<b>£ -</b>
	<b>Summary</b>				
1.0	<b>Preliminaries</b>				£ -
2.0	<b>Demolition/Clearance</b>				£ -
3.0	<b>Construction</b>				£ -
4.0	<b>Restoration</b>				£ -
<b>Total Used For Tender Evaluation Purposes</b>					<b>£ -</b>