

				£	p
INTERNAL WALLS AND PARTITIONS					
<p>The following works are to be read in conjunction with and comply fully with the NBS and all details and notes on Drawings E 17301 A 04 and E 17301 A 19, Preliminaries and General Conditions Refer to Preliminaries for the latest Drawing Revisions</p> <p>100mm blockwork partitions / walls, built up to 200mm above level of suspended ceiling, including damp proof courses, and cutting, toothing and bonding to existing structure</p>					
A	Generally	Item			
140mm blockwork walls, built up to underside of roof structure, including damp proof courses, and cutting, toothing and bonding to existing structure					
B	Generally	Item			
Precast concrete lintels (All Provisional)					
C	100mm x 150mm x 1.2m (2 nr)	Item			
D	140mm x 150mm x 1.31m (6 nr)	Item			
E	140mm x 225mm x 1.31m (11 nr)	Item			
F	140mm x 225mm x 2.15m (1 nr)	Item			
G	140mm x 225mm x 2.4m (2 nr)	Item			
Firestopping					
G1	Firepro firestop compound to tops of block walls built up to underside of roof, 30 minutes fire resisting, as detailed	Item			
G2	Firepro firestop compound to tops of block walls built up to underside of roof, 60 minutes fire resisting, as detailed	Item			
Non itemised works					
H	Allow here for all costs relating to works included on Drawings and in the NBS but not itemised separately in this Section	Item			
INTERNAL WALLS AND PARTITIONS TO PHASE 1 ELEMENTAL SUMMARY £					