Refer to JSA
A1794-JSA-SCH06- Signage schedule for quantities

2 Trail marker front elev
1:10

3 Trail marker side elev
1:10

TRAIL MARKER DOUBLE UNIT SIGN

1 Trail marker plan section A
1:10

TBC what types of unit signs and how many each trail marker will need.
To coordinate with JSA/Client

2.A Trail marker elevation
1:10

TRAIL MARKER SINGLE UNIT SIGN

5 Listening post elev
1:10

6 Listening post side elev
1:10

7 Listening post section
1:10

4 Listening post plan section B
1:10

CDP note:
-The object/detail/construction shown on this drawing constitutes a contractor's design element. Refer to the specification for details.
-All surfaces and edges straight and finely finished.
-No visible welds or fixings.
-Refer to structural design notes for design load requirements.
-Construction component sizes/ sectional sizes are indicative and show aesthetic intent. Any deviation to be agreed with ZMMA.

Key:

1. English oak timber post. Clear UV finish.

2. Galvanised and polyester powder coated metal sheets forming shape with clean square edges. Weather seal finish.

3. Laser-cut graphic symbol. Refer to Graphic Designer information.

4. Direct to media print graphics. Refer to Graphic Designer information.

5. Polyester powder coated mild steel galvanised base and plate.

6. Indicative concrete footing. Contractor's own structural calculations required.

7. Recessed audio panel

8. Recessed solar panels

Notes:

• The design of all the outdoor signage elements is to be robust and to grant sufficient stability to mitigate wind effects.
• The Contractor is to include for structural calculations, including footings.
• Shop drawings to be reviewed by the structural engineer Structures Lab.

Revisions	A	07.08.20	For Tender
	-	01.06.20	Tender first issue

Scale bar

Notes
•Do not scale from this drawing
•Use figured dimensions only
•Dimensions shown in millimetres
•All dimensions given to finished surfaces
•Not to be used as fabrication drawings
•Allow for minimum working tolerances
•Verify all dimensions on site
•Inform Architect of any discrepancies
•Refer to Specification/Finishes Schedule
•Allow for all making good consequent upon the works

For Tender

No. HAF/CO/01 Rev A
Scale 1:10 @ A3
Date March 2020
Project Hainault Forest Interpretation Space

Title Outdoor signage
Trail Marker / Listening Post

ZMMA
HERITAGE FUND
25b Underwood Street
London N1 7LG
T +44 (0)20 7251 8888
F +44 (0)20 7251 8080
E info@zmma.com