1 G1.1 Intro panel elevation
1:20

1No. Intro panel

3 Intro/ Section panels side elevation
1:20

4 Section panels elevation
1:20
G1.2, G2.1, G3.1, G4.1

4No. Section panels

5 Barn object labels side / front elevation
1:5

2 Intro/ Section plan section A (showing posts only)
1:10

Key:

1. Timber posts: sweet chestnut, shaped and joined as shown. Clear finish.

2. 12mm Leathered Richlite. Colour TBC

3. Direct to media print graphics. Refer to Graphic Designer information.

4. Posts to be fixed to barn walls. Discreet fixings to be agreed with ZMMA.

5. Labels discreet split-batten or angled fixing TBA. No visible fixings to the labels' front face.

CDP note:
-The object/detail/construction shown on this drawing constitutes a contractor's design element. Refer to the specification for details.
-All surfaces and edges straight and finely finished.
-No visible welds or fixings.
-Refer to structural design notes for design load requirements.
-Construction component sizes/ sectional sizes are indicative and show aesthetic intent. Any deviation to be agreed with ZMMA.
-The floor construction contains underfloor heating. No floor fixings without prior agreement with ZMMA.
-Maximum load on any wall fixing 50kg, min. 300mm distance between fixings

Revisions
- 07.08.20 For Tender
- 01.06.20 Tender first issue

Scale bar

Notes
•Do not scale from this drawing
•Use figured dimensions only
•Dimensions shown in millimetres
•All dimensions given to finished surfaces
•Not to be used as fabrication drawings
•Allow for minimum working tolerances
•Verify all dimensions on site
•Inform Architect of any discrepancies
•Refer to Specification/Finishes Schedule
•Allow for all making good consequent upon the works

For Tender

No. HAF/CO/05 Rev
Scale varies @ A3
Date March 2020
Project Hainault Forest Interpretation Space

Title Barn Intro/ Section Panels & Labels

ZMMA
HERITAGE FUND
25b Underwood Street
London N1 7LG
T +44 (0)20 7251 8888
F +44 (0)20 7251 8080
E info@zmma.com