

		£	p
SUBSTRUCTURE			
<p>The following works are to be read in conjunction with and comply fully with the NBS and Structural Specification, details and notes on Drawings 29387 200 and 29387 201 and the Preliminaries and General Conditions</p> <p>Refer to Preliminaries for the latest Drawing Revisions</p>			
EXCAVATION AND EARTHWORK			
Excavation, including levelling and compacting all bottoms, herbicidal treatment and keeping free of all water			
A	Excavate oversite to break up pavings and sub-base, including excavating by hand and multiple handling as necessary and removing from site	Item	-
B	Excavate to reduce level, including earthwork supports, excavating by hand and multiple handling as necessary and removing from site	Item	
C	Excavate trenches for ground beams etc, including earthwork supports, excavating by hand and multiple handling as necessary and removing from site	Item	
D	Excavate pits for column bases etc, including earthwork supports, excavating by hand and multiple handling as necessary and removing from site	Item	
E	Excavate pit for Plant Room pit, including earthwork supports, excavating by hand and multiple handling as necessary and removing from site	Item	
F	Excavate pit for Pool, including earthwork supports, excavating by hand and multiple handling as necessary and removing from site	Item	
G	Excavate adjacent to existing building to expose strip footing, including temporary specialist propping to existing building as necessary, earthwork supports, excavating by hand and multiple handling as necessary and removing from site	Item	
H	Extra for breaking up plain concrete at any depth (2 m3 Provisional)	Item	
I	Extra for breaking up reinforced concrete at any depth (2 m3 Provisional)	Item	
J	Extra for breaking up brickwork at any depth (2 m3 Provisional)	Item	
Working Space			
K	Allow for working space and backfilling with hardcore MOT Type 1	Item	

				£	p
	Hardcore filling, MOT Type 1, including compacting				
L	In beds	Item			
M	In backfilling around foundations etc	Item			
	Existing Drainage				
N	Allow for keeping existing drains in full operation, including protection and any temporary diversions necessary	Item			
	CONCRETE WORK				
	Mass Concrete				
O	Filling to bearing strata, to trenches and pits (20 m3 Provisional)	Item			
	Plain In-situ Concrete				
P	Strip foundations	Item			
Q	Pad foundations	Item			
R	Strip foundations to Pool base	Item			
S	Slab, Detail 6	Item			
	Reinforced In-situ Concrete				
T	Strip foundations, Detail 4	Item			
U	Strip foundations, Detail 6	Item			
V	Ground beams	Item			
W	Slab, Detail 5	Item			
	Compressible Material				
X	Filling, Detail 5	Item			
	Beam and Block Floor				
Y	Included elsewhere (Contractor-design)	Item		Info Only	
	BRICKWORK AND BLOCKWORK				
	Blockwork				
Z	100mm sleeper wall, built off existing footing	Item			
AA	215mm sleeper walls	Item			
AB	Composite walls, Details 1, 2 and 3	Item			
	Blockwork and Brickwork				

			£	p
AC	Composite walls, including concrete core, starter bars and mesh reinforcement, Detail 4	Item		
AD	Composite walls, including concrete core, starter bars and mesh reinforcement, Detail 6	Item		
	Brickwork			
AE	Engineering brick piers	Item		
	Ventilation			
AF	Proprietary vents	Item		
	Non itemised works			
AG	Allow here for all costs relating to works included on Drawings and in the NBS and Structural Specification but not itemised separately in this Section	Item		