ORMSKIRK TOWN CENTRE LINK

Description of Works

The works shall comprise the following:

- Site preparation, including providing adequate temporary site security fencing, removal of trees and vegetation in accordance with the recommendations of [ref: Tree Survey & Knotweed Survey]? Removal of existing hand-railing and street lighting columns;
- 2. Excavation of existing earth embankment to facilitate placing of new gabion retaining wall where required;
- 3. Reduced level dig to formation level in widened sections of pathway and under gabion baskets;
- 4. Installing gabion baskets;
- 5. Backfilling and grading earth retained embankment;
- 6. Removal of areas of existing path outside the line of the proposed shared surface;
- 7. Spraying formation/exposed sub-base with residual herbicide in accordance with manufacturer's instruction:
- 8. Placing geotextile membrane over widened section of new path;
- 9. Laying new 75mm PVCu cable duct and draw-pits as required;
- 10. Placing of tantalized timber edging and support pegs;
- 11. Placing and compacting granular sub-base;
- 12. Making good areas of existing path outside the line of the proposed shared surface with clean imported topsoil;
- 13. Placing of NuFlex [or equivalent approved] 50 / 50 mix buff stone /recycled tyres porous surfacing to full width of proposed path;
- 14. Fixing handrail along south-eastern side of new path;
- 15. Installing new street lighting and signage.