## ELMS BANK SPECIALIST ARTS COLLEGE HYDROTHERAPY POOL

				£	р
	FRAME The following works are to be read in conjunction with and comply fully with the NBS and Structural Specification and all details and notes on Drawings 29387 200, 300, 310, 311 and 312, and Preliminaries and General Conditions Refer to Preliminaries for the latest Drawing Revisions				
	Steel Frame				
А	Column, comprising UC 254mm x 254mm x 89kg/m and UB 305mm x 165mm x 40kg/m, grid references 1/F and 1/H	Item			
В	Column, UC 254mm x 254mm x 89kg/m, grid reference 1/J	Item			
С	Column, UB 203mm x 133mm x 30kg/m, between grid references 1/J and 2/J (2 nr)	Item			
D	Column, UC 254mm x 254mm x 89kg/m, grid reference 2/J	Item			
Е	Column, UC 203mm x 203mm x 71kg/m, grid references 2/H and 2/F	Item			
F	Column, UC 254mm x 254mm x 89kg/m, grid references 2/D, 2/C, 2/B and 2/A	Item			
G	Column, UB 203mm x 133mm x 30kg/m, between grid references 2/H and 4/H (1 nr)	Item			
Н	Column, UC 254mm x 254mm x 89kg/m, grid references 4/H, 4/F, 4/D, 4/C, 4/B, 3/B and 3/A	Item			
Ι	Eaves Beam, UB 305mm x 165mm x 40kg/m, between existing building and grid reference 1/F	Item			
J	Eaves Beam, UB 305mm x 165mm x 40kg/m, between grid references 1/F and 1/H	Item			
к	Eaves Beam, UC 152mm x 152mm x 30kg/m, between grid references 1/H and 1/J	Item			
L	Eaves Beam, UC 152mm x 152mm x 30kg/m, between grid references 2/J and 2/H	Item			
Μ	Eaves 1 Beam, UC 152mm x 152mm x 30kg/m, between grid references 2/H and 2/F	Item			
N	Eaves 2 Beam, UC 152mm x 152mm x 30kg/m, between grid references 2/H and 2/F	Item			
0	Eaves 1 Beam, UC 152mm x 152mm x 30kg/m, between grid references 2/F and 2/D	Item			
Ρ	Eaves 2 Beam, UC 152mm x 152mm x 30kg/m, between grid references 2/F and 2/D	Item			

## ELMS BANK SPECIALIST ARTS COLLEGE HYDROTHERAPY POOL

	1	1 1	£p
Q	Eaves 1 Beam, UC 152mm x 152mm x 30kg/m, between grid references 2/D and 2/C	Item	£p
R	Eaves 2 Beam, UC 152mm x 152mm x 30kg/m, between grid references 2/D and 2/C	Item	
S	Eaves 1 Beam, UC 152mm x 152mm x 30kg/m, between grid references 2/C and 2/B	Item	
т	Eaves 2 Beam, UC 152mm x 152mm x 30kg/m, between grid references 2/C and 2/B	Item	
U	Eaves 1 Beam, UC 152mm x 152mm x 30kg/m, between grid references 2/B and 2/A	Item	
V	Eaves 2 Beam, UC 152mm x 152mm x 30kg/m, between grid references 2/B and 2/A	Item	
W	Eaves 1 Beam, UC 152mm x 152mm x 30kg/m, between grid references 2/A and existing building	Item	
х	Eaves 2 Beam, UC 152mm x 152mm x 30kg/m, between grid references 2/A and existing building	Item	
Y	Eaves 1 Beam, UC 152mm x 152mm x 30kg/m, between grid references 3/B and 3/A	Item	
Z	Eaves 2 Beam, UC 152mm x 152mm x 30kg/m, between grid references 3/B and 3/A	Item	
AA	Eaves 1 Beam, UC 152mm x 152mm x 30kg/m, between grid references 3/A and existing building	Item	
AB	Eaves 2 Beam, UC 152mm x 152mm x 30kg/m, between grid references 3/A and existing building	Item	
AC	Eaves 1 Beam, UC 152mm x 152mm x 30kg/m, between grid references 4/H and 4/F	Item	
AD	Eaves 2 Beam, UC 152mm x 152mm x 30kg/m, between grid references 4/H and 4/F	Item	
AE	Eaves 1 Beam, UC 152mm x 152mm x 30kg/m, between grid references 4/F and 4/D	Item	
AF	Eaves 2 Beam, UC 152mm x 152mm x 30kg/m, between grid references 4/F and 4/D	Item	
AG	Eaves 1 Beam, UC 152mm x 152mm x 30kg/m, between grid references 4/D and 4/C	Item	
AH	Eaves 2 Beam, UC 152mm x 152mm x 30kg/m, between grid references 4/D and 4/C	Item	
AI	Eaves 1 Beam, UC 152mm x 152mm x 30kg/m, between grid references 4/C and 4/B	Item	
AJ	Eaves 2 Beam, UC 152mm x 152mm x 30kg/m, between grid references 4/C and 4/B	Item	

## ELMS BANK SPECIALIST ARTS COLLEGE HYDROTHERAPY POOL

					£	р	
AK	Bracing, 12mm x 200mm (2 nr), between columns 1/H and 1/F		Item				
AL	Bracing, 12mm x 200mm (2 nr), between columns 1/C and 1/B		Item				
AM	Bracing, 12mm x 200mm (2 nr), between columns 2/F and 2/D (below Eaves 1)		Item				
AN	Bracing, 12mm x 200mm (2 nr), between columns 2/F and 2/D (above Eaves 1)		Item				
AO	Bracing, 12mm x 200mm (2 nr), between columns 2/C and 2/B (below Eaves 1)		Item				
AP	Bracing, 12mm x 200mm (2 nr), between columns 2/C and 2/B (above Eaves 1)		Item				
	Fire encasement						
AQ	Encasement, half hour resistant, to all exposed steel columns		Item				
	Non itemised works						
AR	Allow here for all costs relating to works included on Drawings and in the NBS and Structural Specification but not itemised separately in this Section		Item				
			FRAME				
TO PHASE 1 ELEMENTAL SUMMARY £							