	UPPER FLOORS The following works are to be read in conjunction with and comply fully with the NBS and Structural Specification and all details and notes on Drawing 29387 300 and Preliminaries and General Conditions Refer to Preliminaries for the latest Drawing Revisions		£	p
	Steel Beams			
А	152mm x 152mm x 23kg/m UC beams	Item		
	Timber joists etc			
В	75mm x 175mm C16 wallplate bolted to existing wall at 400mm centres with, including preparing existing structure	Item		
С	75mm x 175mm C16 joists at 400 mm centres	Item		
D	100mm x 200mm C16 joists at 400 mm centres	Item		
	Floor			
Е	19mm Flooring Grade chipboard fixed to timber joists (12 m2 - Provisional)	Item		
	Non itemised works			
F	Allow here for all costs relating to works included on Drawings and in the NBS and Structural Specification but not itemised separately in this Section	Item		
I	TO PHASE 1 ELE	PER FLOORS SUMMARY £	-	, ,