

		£	p
ROOF			
<p>The following works are to be read in conjunction with and comply fully with the NBS and Structural Specification and all details and notes on Drawings 29387 200, 300, 310, 311 and 312, and Preliminaries and General Conditions</p> <p>Refer to Preliminaries for the latest Drawing Revisions</p>			
Roof Structure			
Steel Rafters			
A	Rafters, UB 356mm x 171mm x 45kg/m, spanning grid references 1/F and 2/F, 1/H and 2/H, and 1/J and 2/J	Item	
B	Eaves haunch connections	Item	
C	Ridge haunch connections	Item	
D	Rafters, UB 305mm x 127mm x 42kg/m, spanning grid references 2/F and 4/F and 2/H and 4/H	Item	
E	Eaves haunch connections	Item	
F	Ridge haunch connections	Item	
G	Rafters, UB 406mm x 178mm x 76kg/m, spanning grid references 2/A and 3/A	Item	
H	Eaves haunch connections	Item	
I	Ridge haunch connections	Item	
J	Rafters, UB 406mm x 178mm x 76kg/m, spanning grid references 2/B and 4/B, 2/C and 4/C, and 2/D and 4/D	Item	
K	Eaves haunch connections	Item	
L	Ridge haunch connections	Item	
Steel Bracing			
M	Bracing, CHS 114.3mm x 8mm, between grid references 1/H, 2/H, 1/J and 2/J	Item	
N	Bracing, CHS 114.3mm x 8mm, between grid references 2/F, 4/F, 2/J and 4/J	Item	
O	Bracing, CHS 114.3mm x 8mm, between grid references 2/B, 4/B, 2/C and 4/C	Item	
Steel Rails			
P	Rail, M235065150, generally, between gridlines 1 and 2	Item	
Q	Rail, M235065150, generally, between gridlines 2 and 3	Item	

R	Rail, M235065150, generally, between gridlines 2 and 4	Item	£	p
	Roof Coverings, Insulation and Rainwater Installations			
S	Included elsewhere (Contractor-design)			Info Only
	Roof Structure			
	Non itemised works			
T	Allow here for all costs relating to works included on Drawings and in the NBS and Structural Specification but not itemised separately in this Section	Item		
TO PHASE 1 ELEMENTAL SUMMARY £			ROOF	-