



KEY TO CEILING TYPES

- MF Ceiling** (u/s 2785mm - to match existing)
1x12.5mm British Gypsum plasterboard and skim lined screw fixed to proprietary Gyproc MF framing.
- MF Continuous Bulkhead Ceiling** (u/s 2495mm)
1x12.5mm British Gypsum plasterboard and skim lined screw fixed to bulkhead proprietary Gyproc MF framing.
- MF Upper Ceiling** (to u/s of existing beam)
1x12.5mm British Gypsum plasterboard and skim lined screw fixed to underside of existing beam with proprietary Gyproc MF framing.
- Metal Open Cell Ceiling** (to u/s of existing beam)
Suggested ceiling finish. Specification and responsibility of installation to be agreed with adjacent tenant.
- Suspended Ceiling**
Suggested ceiling finish. Specification and responsibility of installation to be agreed with adjacent tenant.
- Floor area demised to Greggs with all works within to be carried out by others.

C	05.04.19	Separating walls removed. Roller shutter repositioned.	AM	MS
B	03.03.19	Ticket desk dividing panel varied to glass	AM	MS
A	05.02.19	Ticket desk side panel varied to glass. New door openings and safe room.	AM	MS
REV	DATE	REVISION NOTE	BY	CHECK

